Name: Jefferson Langbid	Date Performed:
Course/Section: CPE 232-CPE31S23	Date Submitted:
Instructor: Dr. Taylar	Semester and SY:
Activity 13: OpenStack Prerequisite Installation	

1. Objectives

Create a workflow to install OpenStack using Ansible as your Infrastructure as Code (laC).

2. Intended Learning Outcomes

- 1. Analyze the advantages and disadvantages of cloud services
- 2. Evaluate different Cloud deployment and service models
- 3. Create a workflow to install and configure OpenStack base services using Ansible as documentation and execution.


3. Resources

Oracle VirtualBox (Hypervisor)

1x Ubuntu VM or Centos VM

4. Tasks

- 1. Create a new repository for this activity.
- 2. Create a playbook that converts the steps in the following items in https://docs.openstack.org/install-quide/
 - a. NTP
 - b. OpenStack packages
 - c. SQL Database
 - d. Message Queue
 - e. Memcached
 - f. Etcd
 - g. Create different plays in installing per server type (controller, compute etc.) and identify it as a group in Inventory file.
 - h. Add, commit and push it to your GitHub repo.
- **5.** Output (screenshots and explanations)



I created a new github repository

```
Jefferson@LocalMachine: ~/HOA1


GNU nano 6.2 ansible

Idefaults]

inventory = inventory
host_key_checking = False

deprecation_warnings = False

ansible_user = jefferson
private_key_file = ~/.ssh/
```



I created the ansible.cfg and inventory for the ansible.

```
GNU nano 6.2


OpenStack.yml


- hosts: all
become: true
pre_tasks:


- name: Install updates for Ubuntu
tags: always
apt:
    update_cache: yes
changed_when: false
when: ansible_distribution == "Ubuntu"
```

I created the yml of the ansible


I created the roles for the installation of OpenStack














```
TASK [NTP : Editing the chrony file for ubuntu] ********************************
^[OPchanged: [192.168.56.104]
changed: [192.168.56.104]
changed: [192.168.56.104]
TASK [Memcached : Starting Memcached for ubuntu] ********************************
changed: [192.168.56.104]
```

The code ran successfully and installed the OpenStack prerequisites.

```
jefferson@Server2:~$ sudo systemctl status rabbitmq-server
rabbitmg-server.service - RabbitMQ Messaging Server
     Loaded: loaded (/lib/systemd/system/rabbitmq-server.service; enabled; ven
     Active: active (running) since Wed 2022-12-07 20:14:08 PST; 26min ago
   Main PID: 7996 (beam.smp)
     Tasks: 21 (limit: 1080)
     Memory: 31.3M
        CPU: 16.566s
     CGroup: /system.slice/rabbitmq-server.service
              -7996 /usr/lib/erlang/erts-12.2.1/bin/beam.smp -W w -MBas ageffc
              -8007 erl child setup 65536
              -8055 inet_gethost 4
             └─8056 inet_gethost 4
Dec 07 20:14:02 Server2 systemd[1]: Starting RabbitMQ Messaging Server...
Dec 07 20:14:08 Server2 systemd[1]: Started RabbitMO Messaging Server.
lines 1-15/15 (END)
                                                  jefferson@Server2:~$ sudo systemctl status mysql
mariadb.service - MariaDB 10.6.11 database server
    Loaded: loaded (/lib/systemd/system/mariadb.service; enabled; vendor pres>
    Active: active (running) since Wed 2022-12-07 20:33:27 PST; 7min ago
      Docs: man:mariadbd(8)
            https://mariadb.com/kb/en/library/systemd/
  Main PID: 26008 (mariadbd)
    Status: "Taking your SQL requests now..."
     Tasks: 7 (limit: 1080)
    Memory: 40.8M
       CPU: 889ms
    CGroup: /system.slice/mariadb.service
             —26008 /usr/sbin/mariadbd
jefferson@Server2:~$ sudo systemctl status nove-compute
Unit nove-compute.service could not be found.
jefferson@Server2:~$ sudo systemctl status nova-compute
nova-compute.service - OpenStack Compute
    Loaded: loaded (/lib/systemd/system/nova-compute.service; enabled; vendor>
    Active: active (running) since Wed 2022-12-07 20:21:02 PST; 20min ago
  Main PID: 23156 (nova-compute)
     Tasks: 2 (limit: 1080)
    Memory: 33.4M
       CPU: 3.841s
    CGroup: /system.slice/nova-compute.service
             -23156 /usr/bin/python3 /usr/bin/nova-compute --config-file=/etc
Dec 07 20:21:02 Server2 systemd[1]: Started OpenStack Compute.
Dec 07 20:21:06 Server2 nova-compute[23156]: Modules with known eventlet monke>
lines 1-12/12 (END)
```

```
jefferson@Server2:~$ sudo systemctl status chronyd
chrony.service - chrony, an NTP client/server
     Loaded: loaded (/lib/systemd/system/chrony.service; enabled; vendor prese>
    Active: active (running) since Wed 2022-12-07 20:33:48 PST; 8min ago
      Docs: man:chronyd(8)
            man:chronyc(1)
            man:chrony.conf(5)
  Main PID: 26964 (chronyd)
     Tasks: 2 (limit: 1080)
    Memory: 1.5M
       CPU: 54ms
     CGroup: /system.slice/chrony.service
            26964 /usr/sbin/chronyd -F 1
26965 /usr/sbin/chronyd -F 1
jefferson@Server2:~$ chronyc -n sourcestats -v
                           .- Number of sample points in measurement set.
                              .- Number of residual runs with same sign.

    Length of measurement set (time).

                                        .- Est. clock freq error (ppm).
                                                   .- Est. error in freq.
                                                            .- Est. offset.
                                                               On the -.
                                                                samples. \
Name/IP Address
                         NP NR Span Frequency Freq Skew Offset Std Dev
------
jefferson@Server2:~$ sudo systemctl status etcd
etcd.service - etcd - highly-available key value store
    Loaded: loaded (/lib/systemd/system/etcd.service; enabled; vendor preset:>
    Active: active (running) since Wed 2022-12-07 20:35:25 PST; 7min ago
      Docs: https://etcd.io/docs
            man:etcd
  Main PID: 28561 (etcd)
     Tasks: 6 (limit: 1080)
    Memory: 5.6M
       CPU: 3.095s
    CGroup: /system.slice/etcd.service
            └─28561 /usr/bin/etcd
```

Proofs that the prerequisites are already installed.

```
jefferson@LocalMachine: ~/HOA13_o/OpenStack
Untracked files:
  (use "git add <file>..." to include in what will be committed)
no changes added to commit (use "git add" and/or "git commit -a")
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/ETCD/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ got add roles/Memcached/
Command 'got' not found, but there are 17 similar ones.
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/Memcached
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/Messqueue/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/Memcached/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/NTP/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/OS/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git add roles/SQLDB/
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git commit -m "HOA13"
[main 04fa4f7] HOA13
6 files changed, 191 insertions(+)
create mode 100644 OpenStack/roles/ETCD/tasks/main.yml
create mode 100644 OpenStack/roles/Memcached/tasks/main.yml
 create mode 100644 OpenStack/roles/Messqueue/tasks/main.yml
 create mode 100644 OpenStack/roles/NTP/tasks/main.yml
 create mode 100644 OpenStack/roles/OS/tasks/main.yml
 create mode 100644 OpenStack/roles/SQLDB/tasks/main.yml
jefferson@LocalMachine:~/HOA13_o/OpenStack$ git push origin main
```

I added, committed, and pushed it to my github repository.

jlangbid13/HOA13 o (github.com)

Reflections:

Answer the following:

What are the benefits of implementing OpenStack?
 The benefits of Implementing Openstack is that it has few prerequisites that are needed. As long as you have the internet you can use it in the cloud servers. It also has high data security, reliability, scalable storage volume and performance.

Conclusions:

All in all, in this activity, we are tasked to install the prerequisites of openstack using ansible to another server. First, I created a github repository and cloned it to the local machine and also created the ansible.cfg and then the inventory for the ansible. After that I created the roles for the computer and controller. I created the yml for the installation of the prerequisites which are NTP, OpenStack packages, SQL database, Message Queue, memcached, and Etcd. I created the role directory to store the

main.yml of each role and after inputting the codes the ansible ran successfully. I added, committed, and pushed the files to my github repository